MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Notification dated 9th December 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executitve Engineer, Mysore Railways, Mysore, on any working day up to 12 Noon on Monday, the 13th January 1936, for constructing (i) Menials Quarters, one Block of two units and (ii) Sweepers Quarters one Block of one unit at Chamarajanagar on Mysore-Chamarajanagar Section. Approximate estimates of quantities are given in the schedule printed below. The quantites are not guaranteed. The building or buildings must be completed by the 1st May 1936, showing monthly progress as noted in the tender.

2. Detailed estimates, plans and specifications and conditions of works and conditions of Schedule Agreement may be seen at the Senior Executive Engineer's Office, Mysore Railways, Mysore, on all working days between 10-30 A.M. and 4-30 P.M. When in doubt, the tenderers should always ask for particulars and details.

3. Tenders should be submitted on printed forms, which may be obtained in ample time from the Senior Executive Engineer's Office, on production of a receipt for payment of rupee one to the Auditor, Mysore Railways, Mysore.

4. Every tender must be accompanied by an earnest money of Rs. 100 which should be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender and should be superscribed " Tender for constructing Menials and Sweepers Quarters at Chamarajanagar " in default of which tenders will be rejected. Tenderers who have not done work previously in this department should produce certificates from authorities regarding their capacity for work and execution.

5. The earnest money of the rejected tenders will be returned as early as possible after the tenders are disposed of, and in the case of accepted tender, it will be held as a part security deposit under Clause 4 of the Schedule Agreement referred to in para 8.

6. The final acceptance of the tender rests with the Superintendent, Way and Works, (or Agent, as the case may be) Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender. He also reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders or any portion of a tender and also the right to accept a tender for any individual item or items without accepting the whole tender, unless the tenderer expressly states in his tender that it must be accepted or rejected as a whole.

7. The name of the contractor, whose tender has been accepted, will be posted on the Notice Board in the Senior Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful tenderer is required to execute the usual Schedule Agreement in default of which his tender will be considered as cancelled and the earnest money forfeited to Government.

9. Quotations must be given in words as well as in figures and they must be in specific terms of unit shown against each item of work. Any quotation quoted at so much per cent less or more than the estimated rates will not be accepted.

10. Rates once tendered cannot be enhanced on any account. Rates for non-tendered and non-estimated items shall be as per schedule of rates of the Railway Department or those fixed by the Senior Executive Engineer after working out data with 10 per cent for contractor's profit.

11. The whole of the work specified in the Agreement to be completed as specified in para 1 above, failing which or failing to carry out any of the conditions in the Agreement, the whole of the money held in deposit or so much of it as the Agent, Mysore Railways, Mysore, considers proper will, without prejudice to any other legal or equitable right or remedy which the Agent may have, be absolutely forfeited to the Agent, Mysore Railways, Mysore.

12. Should any dispute arise in the interpretation of the clauses of the tender or in respect of any item of work or specification, the decision of the Superintendent, Way and Works, Mysore Railways, Mysore, shall be final.

13. The accepted tenderer must make his own arrangements in advance for payment of royalties, etc., in case the quarries stone, earth, kunker, sand, etc., from Railway, Government or Forest land for use on this work, as this department will not concern itself regarding the payment, recovery, etc.

14. Attention is invited to the three foot-notes.

Schedule.

Sl. No	Details of work	Quantity	Unit
	I. Constructing Menials Quarters one Block of 2 Units at Chamarajnagar.		
1	Earthwork excavation and filling in	2,900 C.ft.	1,000 C.ft.
2	Collecting and spreading sand and watering, tamping, complete for foundation	600 C.ft.	100 C.ft.
3	Concrete, broken stone jelly in chunam mortar	900 ,,	100 ,,
4	Burnt brick in sand mortar	1,200 ,,	100 ,,
5	Burnt brick in clay	1,150 ,,	100 ,,
6	Burnt stone slabs 6" thick, one line dressed and fixed in mortar ..	250 S.ft.	1 S.ft.
7	Teakwood doors battened with 1" thick shutters and all fittings complete as per specification	36 ,,	1 ,,

Sl. No.	Details of work	Quantity	Unit
8	Teakwood windows, battened with 1″ thick shutters with ¾″ square mild steel bars fixed at not more than 4″ centres and with all fittings complete as per specification	42 C.ft.	1 C.ft.
9	Teakwood wrought and put up including wood oiling, two coats	43 „	1 „
10	Roofing with first class Mangalore pattern Yelahanka tiles on teak-wood reepers 2″×1″ including chunnam borders, teakwood wind ties and wood oiling reepers, complete	800 S.ft.	100 S.ft.
11	Ridge tiles, Mangalore pattern, set in mortar including cement pointing.	27 R.ft.	1 R.ft.
12	Chunam plastering	3,000 S.ft.	100 S.ft.
13	White-washing, two coats	3,000 S.ft.	100 „
14	Flooring with 6″ thick chunam concrete with ½″ thick cement plastering	380 S.ft.	100 „
15	Hoisting and fixing 41¼ lbs. section second-hand departmental rails.	66 R.ft.	1 R.ft.
16	Providing ovens	No. 2	No. 1
17	Providing and fixing granite stone mortar and pestle	No. 2	„ 1
18	Painting with silicate chocolate, two coats	220 S.ft.	100 S.ft.
19	Teakwood finials	No. 2	No. 1
20	Providing and fixing smoke tiles	4 „	„ 1
21	'U' shaped drain 6″×8″ in Burnt brick in mortar and plastered over with cement	30 R.ft.	1 R.ft.
22	Providing soak pits (3′×3′×3′)	No. 2	No. 1
23	Providing teakwood shelves with 1″ thick shutters, etc., complete	15 S.ft.	1 S.ft
	II. Constructing Sweepers Quarters 1 Block of 1 Unit at Chamarajanagar.		
1	Earthwork excavation and filling in	1,500 C.ft.	1,000 C.ft.
2	Collecting and spreading sand and watering tamping complete for foundations	320 C.ft.	100 C.ft.
3	Concrete broken stone and jelly in chunam mortar	435 „	100 „
4	Burnt brick in sand mortar	530 „	100 „
5	Burnt brick in clay	520 „	100 „
6	Burnt stone slabs 6″ thick, one line dressed and fixed in mortar	150 S.ft.	1 S.ft.
7	Teakwood doors battened with 1″ thick shutters and all fittings complete as per specification	18 „	„
8	Teakwood windows, battened with 1″ thick shutters with ¾″ sqr. mild steel bars fixed at not more than 4″ centres and with all fittings complete as per specification	18 „	„
9	Teakwood wrought and put up including wood oiling two coats complete	17 C.ft.	1 C.ft.
10	Roofing with 1st Class Mangalore pattern Yelehanka tiles on teak-wood reepers 2″× 1″ including chunnam borders, teakwood wind ties and wood oiling to reepers	380 S.ft.	100 S.ft.
11	Ridge tiles, Mangalore pattern, set in mortar including cement pointing.	52 R.ft.	1 R.ft.
12	Chunam plastering	1,340 S.ft.	100 S.ft.
13	White-washing, two coats	1,340 S.ft.	„
14	Flooring with 6″ thick chunam concrete with cement plastering ½″ thick	140 S.ft.	„
15	Providing ovens	No. 1	No.
16	Providing and fixing granite stone mortar and pestle	No. 1	„
17	Painting with silicate chocolate, two coats	100 S.ft.	100 S.ft.
18	Providing and fixing smoke tiles	No. 2	No.
19	'U' shaped drain 6″×8″ in Burnt brick in mortar and plastered over with cement	20 R.ft.	1 R.ft.
20	Providing teakwood shelves with 1″ thick shutters, etc., complete	8 S.ft.	1 S.ft.
21	Providing soak pits (3′×3′×3′)	No. 1	No.

(i) Work should be completed as per Marryats Specifications.

(ii) Railway materials concession certificates will be issued for roofing tiles to Chamarajanagar from the place of despatch.

(iii) Measurements for doors, windows, etc., will be given for clear openings only and so the tenderers have to quote suitably.

R. N. MIRZA,
Senior Executive Engineer.